

**Notice Inviting Quotation:**

Sealed quotation are invited for the following works from experienced bonafied and resourceful outside /inside contractors for the under mentioned works by the The Chief Executive Office of The Tollygunge Club Ltd. 120 Deshapran Sasmal Road, Kolkata-700 033.

**Name of the work:** Renovation and Up-gradation of South Indian and Juice Counter near entrance part of Main Lawn of Tolly gunge Club as per attached layout plan.

| Sl no.                                  | Description of work  | Unit | Qty  | Rate in figure in Rs. | Rate in words | Total Amount in Rs. | Remarks |
|---|--|------|------|-----------------------|---------------|---------------------|---------|
| 1                                       | Taking out old damage M S structure along with partitions of Juice and Dosa counter including all types of metal sheet, false ceiling, roof sheet , brick wall, granite counter etc including removing and stacking the same as directed . Stacking the dismantable materials upto 150 m from work site.                       | sft  | 400  |                       |               |                     |         |
| 2                                       | Earth work in excavation for foundation trenches upto 750mm level from Ground level.   | Cft  | 850  |                       |               |                     |         |
| 3                                       | Single layer brick flat soling with sand after the dressing of the existing floor soil.  | Sqft | 410  |                       |               |                     |         |
| 4                                       | Providing and laying of 50mm thick PCC over the soling with 1:3:6 cement sand and stone chips ration maintain the line level.  | Sqft | 410  |                       |               |                     |         |
| 5                                       | One or more brick ( 1st class) thick wall infoundation and plinth with cement mortar 1:5 ( 1 cement : 5 sand)  | Cft  | 200  |                       |               |                     |         |
| 6                                       | 125mm thick brick(1st class) wall in superstructure with cement mortar 1:5   | Sqft | 900  |                       |               |                     |         |
| 7                                       | 250 x250 brick (1st class) column in superstructure with cement mortar 1:5.  | Cft  | 100  |                       |               |                     |         |
| 8                                       | RCC 1:1.5:3 Lintel with 12mm (4nos) & 8mm dia. Stirrup @15 c/c TMT bar over brick wall at an height 7 feet shuttering complete. TMT bars will be Tata or Sail make.  | Rft  | 125  |                       |               |                     |         |
| 9                                       | Providing and applying of sand cement plaster with 1:5 cement sand ratio on the chemical applied area of 15mm average thickness to match the same level of the existing plastered surface and keeping 2mm drop for puty application.   | sft  | 1800 |                       |               |                     |         |
| 10                                      | Fabrication,erection MS hollow frame structure for ranigunge tiles laying with necessary welding complete. Used Tata/Sail make Hollow MS section.  | Kg   | 1200 |                       |               |                     |         |
| 11                                      | Providing and laying clay Ranigunge roof tiles ( 1st class) and ridge tiles to roof surface with necessary fittings complete.  | Sqft | 600  |                       |               |                     |         |
| 12                                      | Providing and laying 10mm thick cement fibre board of Avest make with necessary fitting and joint filling with approved joint filling materials below  | Sqft | 600  |                       |               |                     |         |
| 13                                      | Providing and laying of 20mm thick Kota stone on the floor with 1:5 cement sand mortar including polishing all complete.   | Sqft | 500  |                       |               |                     |         |
| 14                                      | Wall tiles- providing ,fitting and fixing of wall tiles of Kajaria, Nitco,Jonshon make with 1:5 cement sand mortar or tiles fixing chemical.   |      |      |                       |               |                     |         |
| a                                       | Tiles kor kitchen wall : ( Basic price : Rs. 45/- per sft)   | Sqft | 300  |                       |               |                     |         |
| b                                       | Other than kitchen area: ( Basic price : 60/- per sft)   | Sqft | 800  |                       |               |                     |         |
| 15                                      | Providing and fixing of 50mm thick Aluminium partition with 5mm glass at top and ACP board on bottom at kitchen area.  | Sqft | 110  |                       |               |                     |         |
| 16                                      | Glass door- 12mm thick toughened glass door with floor spring and necessary hardware and fittings of Hardwyn make. ( Size : 3' x 7')   | Nos  | 4    |                       |               |                     |         |
| 17                                      | False ceiling work with GI frame structure and 12mm thick POP board will be hanged from the metal framed structure all complete with taping and  | Sqft | 415  |                       |               |                     |         |
| 18                                      | Providing and applying of 2-3mm thick exterior grade dust putty Berger/Dulux/Asian paint make over the new plastered area.   | sft  | 1500 |                       |               |                     |         |
| 19                                      | Providing and applying of 2 coats of primer and 2 coats of exterior paint of Berger/Dulux/Asian paint make after the application of acrylic putty on all   | sft  | 1700 |                       |               |                     |         |
| 20                                      | Providing and laying of 15mm thick granite counter with 20mm granite of basic price Rs. 180 per sft with karappa black stone with metal section for the  | Sqft | 130  |                       |               |                     |         |
| 20                                      | Glass door- 12mm thick toughened glass door with necessary hardware and fittings of Hardwyn make.  | Nos  | 4    |                       |               |                     |         |
| 21                                      | Glass partition- providing and fixing glass partition on the wall after 900mm with cut out for sale purpose of 12mm thick toughened glass to be fixed with   | Nos  | 150  |                       |               |                     |         |
| 22                                      | False ceiling work with GI frame structure and 12mm thick Indian Gypsum board will be hanged from the metal framed structure all complete with taping and jointing.  | Sqft | 415  |                       |               |                     |         |
| 23                                      | Internal plumbing work for the water supply and drainage line for sinks as per the direction of project in charge with UPVC pipe and sockets. The rate including 3 Nos 22"x20" SS Sink and Sink Cock all complate with angular stop cock and valves. Sink makes : Nirala, Pipe : Supreme make, Plumbing fittings: Jaquor make. | LS   | 1    |                       |               |                     |         |
| <b>Total Amount (Excluding GST) Rs.</b> |  |      |      |                       |               |                     |         |

**Total Amount Rs.**

**Terms & Condition:**

1. Sealed quotation to be submitted at Club Office 1st floor on or before 22nd May'24.
2. Completion time : 50 days.
3. Payment will be made against RA bill/ Final bill.
4. 5% retention money to be hold up to defect liability period.
5. Current ESI & PF chalan to be submitted with each bill.
6. In case the work is not completed on or before the date of completion stated above a penalty of 0.5% of the total bill value will be deducted per week of the incomplete portion of work up to a maximum 5% of the incomplete portion of work.
7. Please note that you have to mandatorily submit all necessary documents ( as per law) along with your bills being conclusive proof that you are fully GST compliant as will be required from time to time failing to which this work order will be unilaterally cancelled by the Club and the Club will not be responsible for any financial loss incurred on your behalf.
8. All safety Protocols to be strictly followed during work.

**Mr. Subrato Banerjee**  
Chief Manager- HR & Administration  
Tollygunge Club Ltd.  
Contact : 2473 2316 , Extn. 408

**Signature of Contractor with seal**

